



PLUMBING NOTES
 ALL VENTS 1 1/2" E.A.N.
 ALL SEWAGE PIPING SCH. 40 PVC INCL. FITTINGS
 DRAIN EWH RELIEF AND PAN INTO MDP SINK
 ALL SUPPLY LINES TO BE COPPER
 USE S.S. 1/2"-3/8" S.D. VALVES DN ALL FIXTURES

JOB DESCRIPTION
 THESE PLANS COVER THE CONSTRUCTION OF A NEW BASEBALL FIELDHOUSE FOR THE UNIVERSITY OF RIO GRANDE.

USE GROUP=S-1/B
 CDNST. TYPE=3B
 AREA=4426 S.F.
 OCCUPANCY=

ROOM FINISHES
 CEILINGS=26GA. RIBBED METAL EXCEPT 5/8" 'X' GYPSUM IN CORRIDORS/STAIRWELL AND 5/8" ACT IN RESTROOMS
 WALLS: EXTERIOR: GROUND FLOOR=MASONRY, SECOND FLOOR=GYPSUM
 INTERIOR: GYPSUM EXCEPT FRP IN RESTROOMS, LOCKER ROOM
 FLOOR: CONCRETE SLAB (GRD. LEVEL)
 ADVANTECH® FLOORING (UPPER LEVEL)

DOOR SCHEDULE
 (A) 3/0x7/0 METAL DN METAL FRAME (FOR MASONRY), NO GLASS, CLOSER, NDT RATED, ADA THRESHOLD, ADA LEVER HDW, R-5 INS.
 (B) 3/0x6/8 METAL DN METAL FRAME, NO GLASS, 20MIN. RATED, ADA LEVER HDW
 (C) 3/0x6/8 METAL DN METAL FRAME, NO GLASS, 1HR. RATED, ADA LEVER HDW
 (D) 3/0x6/8 METAL DN METAL FRAME, NO GLASS, NDT RATED, ADA THRESHOLD, ADA LEVER, R-5 INS.
 (E) 7/0x9/0 METAL OVERHEAD DOOR W/ R-5 INS., METAL TRACK, NDT RATED
 (F) 3/0x7/0 METAL DN METAL FRAME (FOR MASONRY), NO GLASS, CLOSER, NDT RATED, STANDARD THRESHOLD, ADA LEVER HDW, R-5 INS.

BRECH ENGINEERING

* 1828 EASTERN AVE. * GALLIFOLIS, OHIO 45631 *
 * (740) 446-0059 VOICE * (740) 446-1889 FAX *

BRIDGET HARRIS
 CHECKED BY
 R.G. BRECH, P.E.
 SCALE AS NOTED
 DATE 08/28/12
 PROJECT NO. 12-0000000000

UNIVERSITY OF RIO GRANDE
 BASEBALL FIELDHOUSE
 RIO GRANDE, OHIO